



DEPARTMENT OF THE ARMY
NEW ENGLAND DIVISION, CORPS OF ENGINEERS
424 TRAPELO ROAD
WALTHAM, MASSACHUSETTS 02254

REPLY TO
ATTENTION OF:

NEDED-F

18 December 1981

SUBJECT: Reconnaissance Report, Surry Mountain Dam, Keene, NH

CDR (DAEN-CWO-M)
WASH, DC 20314

In accordance with ER 1110-2-417, there is submitted for review and approval Reconnaissance Report, Surry Mountain Dam, located in the Connecticut River Basin, Ashuelot River, Keene, New Hampshire. As recommended in paragraph 6, a reply by 20 January 1982 would be appreciated to allow for subsequent activities to proceed as scheduled.

FOR THE COMMANDER:

Inclosure (10 cys)
As stated


✓ JOE B. FRYAR, P. E.
Chief, Engineering Division

EARTHQUAKE DESIGN AND ANALYSIS FOR CORPS OF ENGINEERS DAMS

RECONNAISSANCE REPORT

FOR A

SPECIAL ENGINEERING INVESTIGATION

SURRY MOUNTAIN DAM

KEENE, NH

**US Army Corps
of Engineers**

New England Division

Engineering Division

Geotechnical Engineering Branch

Waltham, Massachusetts 02254

December 1981



TABLE OF CONTENTS

	<u>PAGE</u>
1. AUTHORITY	1
2. PURPOSE	1
3. CURRENT STATUS	1
4. EMBANKMENT AND FOUNDATION	1
5. PRELIMINARY SEISMIC ANALYSES	2
6. RECOMMENDATION FOR A SPECIAL ENGINEERING INVESTIGATION	3

EXHIBITS

- A. STATUS OF SEISMIC EVALUATION AND ANALYSES OF EXISTING DAMS
- B. SUMMARY OF EMBANKMENT AND FOUNDATION CONDITIONS
- C. BORING LOGS AND LABORATORY TEST RESULTS
- D. PSEUDO-STATIC EARTHQUAKE STABILITY ANALYSES

1. AUTHORITY. The authority for this study and report is contained in the following:

ER 1110-2-1806, Earthquake Design and Analysis for Corps of Engineers Dams, 30 April 1977.

ER 1130-2-417, Major Rehabilitation and Dam Safety Assurance Program, 30 November 1980.

EC 1110-2-229, Special Engineering Investigations, Dam Safety Assurance Program, 18 March 1981.

2. PURPOSE. Earthquake analyses performed to date indicate a potential safety problem at Surry Mountain Dam under earthquake induced loading. The purpose of this report is to justify the need for a special engineering investigation.

3. CURRENT STATUS. The current status of the New England Division's seismic evaluations and analyses program was presented in letter to the Commander, U. S. Army Corps of Engineers, DAEN-CWE-SS, dated 14 July 1981 in response to a letter request from the Chief, Engineering Division, Director of Civil Works dated 11 June 1981 (Exhibit A). The reply letter affirmed that thirty-five completed New England Division dams which were analysed by the pseudo-static method in accordance with the criteria in ER 1110-2-1806, have adequate factor of safety. Six of the thirty-five dams were also analysed for liquefaction and cyclic mobility potential and three out of six were found to have a potential seismic instability problem; these dams are: Knightville, Surry Mountain and West Thompson. The dynamic stability analysis of Knightville Dam is in progress and scheduled for completion in October 1982; Surry Mountain and West Thompson are scheduled for investigation in FY-82 and 83 respectively.

4. EMBANKMENT AND FOUNDATION

a. General. Surry Mountain Dam was constructed in 1939-41 and designed by the U. S. Engineer Office, Providence, RI; Re: "U. S. Army Corps of Engineers Design Memorandum, Connecticut River Flood Control, Surry Mountain Dam, Ashuelot River, NH: Analysis of Design", July 1939. A summary of embankment and foundation conditions extracted from the Analysis of Design is in Exhibit B.

b. Dam Embankment. The dam embankment is a rolled-earth-fill 86 feet maximum height approximately 1,800 feet long, consisting of a central impervious core flanked by random impervious and pervious shells. (Exhibit B).

c. Foundation Conditions. The foundation is composed of three types of glacial sediments; stratified outwash sand and gravel, glacial till and glacial lake deposits of uniform fine sand and silt (Exhibit B), overlaying rock which is about 100 foot depth at the center of the valley and left abutment and rock outcropping on the right abutment. Deposits of loose, low strength, finely textured fine sand and silt occupy a prominent portion of the dam foundation.

On account of the low strength and the possibility of plastic flow or large deformation of the foundation during embankment construction it was decided during design to construct the embankment over a two construction season period to allow weaker soils to gain strength through consolidation. During the first season, the cut off trench was constructed and the site was prepared for embankment construction; the embankment was constructed during the following two construction seasons. Two borings at the landside toe of the embankment made during the 1980-81 investigation (Exhibit C) disclosed low penetration (SPT) resistance values in the foundation fine sand and silt deposit.

5. PRELIMINARY SEISMIC ANALYSES

a. General. Seismic analyses of Surry Mountain Dam were made under the New England Division program of seismic evaluation of its existing dams. The following investigations have been completed to date and copies of the reports have been furnished to Headquarter, Department of the Army (DAEN-CWE-SS).

(1) Remote Sensing Analysis of Fault-Related Structures in New England and Related Seismic Hazards at Corps of Engineers Projects, October 1978.

(2) Low-Sun Angle Aerial Reconnaissance of Faults and Lineaments of Southern New England, September 1980.

(3) Stability Analysis by the Seismic Coefficient Method, Completed New England Division Dams, August 1980.

(4) Liquefaction and Cyclic Mobility Potential, Completed New England Division Dams, Phase I Investigation, September 1980; Phase II Investigation February 1981.

b. Pseudo-static Analysis. A pseudo-static earthquake stability analysis was performed for the steady seepage condition with reservoir pool elevations at the critical pool level and at the maximum pool level for the upstream and downstream dam embankment slopes respectively (see Exhibit D). The minimum computed factors of safety are higher than the required minimum of 1.00 and are as follows:

<u>Condition</u>	<u>Seismic Coefficient</u>	<u>Downstream Slope Factor of Safety</u>	<u>Upstream Slope Factor of Safety</u>
Static	-	1.86	2.03
Pseudo-static	0.05	1.50	1.61
"	0.10	1.26	1.32
"	0.13	1.15	1.19

The seismic coefficient of 0.05 was selected for stability analysis from the Seismic Risk Map in ER 1110-2-1806, the 0.10 coefficient is the next higher value selected from the risk map as directed by the OCE for use in the seismic stability analysis. The 0.13 coefficient used in the stability analyses was derived by using a predicted peak acceleration determined by increasing the

recorded Mercalli intensity by one unit; the value thus obtained was attenuated to the site.

c. Liquefaction and Cyclic Mobility Potential. The investigation completed in 1981 (Exhibit B) included two foundation borings, laboratory testing of undisturbed samples and a study on the potential for cyclic mobility and liquefaction. The borings disclosed penetration resistances (SPT) values in the range of 2 to 10 blows per foot (pulley and cathead with a sleeve type hammer) in foundation soil zones of fine sand and silt. These low SPT values indicate a possible potential for liquefaction (see page 4). Cyclic and monotonic triaxial test results performed on undisturbed soil samples indicated that contractive volume changes may occur in the loose fine sand and silt zones of the dam foundation with a potential of liquefaction and cyclic mobility. Page 5 shows a typical curve for contractive and dilative soil. Results of the investigation led to a recommendation for execution of a dynamic analysis of the dam (Exhibit B).

6. RECOMMENDATION FOR A SPECIAL ENGINEERING INVESTIGATION

The investigations performed to date have disclosed that there may be a dam safety problem at Surry Mountain Dam because of the potential for liquefaction and cyclic mobility of its foundation. A special engineering investigation is needed to identify the extent and severity of the problem and the need for remedial construction work. The special engineering investigation will consist of borings, field seismic work, seismicity investigation, laboratory testing and response analysis. Funding for the investigation has been included in the New England Division O&M Budget for FY 82 and a cost estimate breakdown is as follows:


a. Work by Contract (Scheduled for Award in April 1982)

Field Borings and Seismic	\$ 70,000 ✓	
Laboratory Testing	80,000 ✓	
Geology and Seismicity	50,000 ✓	
Response Analysis	50,000	
Reports and other costs	30,000	
	<hr/>	
Total est. A-E cost	\$280,000	

b. In-House Cost

Recon. Report and Contract Specs.	20,000
Contract management and review work	45,000
	<hr/>
Total est. in-house cost	54,000

c. <u>Total Cost</u>	\$345,000
----------------------	-----------




LEGEND:

- Liquefaction - stress ratio based on $R_D=0.8$ and acceleration of 0.13g, 0.10g and 0.05g at 27 feet below ground surface.
- △ Liquefaction - stress ratio based on $R_D=0.8$ and acceleration of 0.13g, 0.10g and 0.05g at 36 feet below ground surface.

CORRELATION BETWEEN STRESS RATIO ASSUMING TO CAUSE LIQUEFATION
IN THE FIELD AND PENETRATION OF SAND (SEED, 1976)

EFFECT OF INITIAL VOID RATIO ON STRESS-STRAIN CURVE UNDRAINED LOADING



GEI-077-575

Chart taken from G E I "Analysis of embankment and soil foundations for earthquake loading" March 14-15, 1978.

EXHIBIT A

EXHIBIT A

STATUS OF SEISMIC EVALUATIONS AND ANALYSES OF EXISTING DAMS

TABLE OF CONTENTS

<u>SUBJECT</u>	<u>PAGE</u>
Office of the Chief of Engineers ltr dated 11 June 1981	A-1
New England Division ltr dated 14 July 1981	A-3
Existing NED Dams Investigated under ER 1110-2-1806 - Table I	A-5
Status of Seismic Evaluations and Analyses of NED Dams - Table II	A-7



DEPARTMENT OF THE ARMY
OFFICE OF THE CHIEF OF ENGINEERS
WASHINGTON, D.C. 20314

REPLY TO
ATTENTION OF:

DAEN-CWE-SS

11 June 1981

SUBJECT: Status of Seismic Evaluations and Analyses of Existing Dams

SEE DISTRIBUTION

1. Reference ER 1110-2-1806, 30 April 1977, Earthquake Design and Analysis for Corps of Engineers Dams.
2. The referenced regulation is currently being revised and the status of seismic evaluations is needed to accomplish the revision. Each division should review the status of the investigations and evaluations being performed and submit a revised schedule for completion of the program. This revised schedule should include all projects studied, completed and planned by name and purpose, type of structure, date the investigation was or will be started, date completed or planned completion date, the magnitude of the design earthquake at the site, and actual or planned cost of the investigation and/or evaluation. Projects that have been excluded from this program should be listed separately.
3. In cases where ongoing seismic evaluations will lead to future comprehensive studies and/or remedial measures, the report should be submitted to this office for approval.
4. The schedule should be submitted to DAEN-CWE-S by 15 July 1981. The funding summary should be furnished not later than 15 September 1981.

FOR THE CHIEF OF ENGINEERS:

LLOYD A. DUSCHA, P.E.
Chief, Engineering Division
Directorate of Civil Works

DISTRIBUTION
See Page 2

DAEN-CWE-SS

11 June 1981

SUBJECT: Status of Seismic Evaluations and Analyses of Existing Dams

DISTRIBUTION:

Division Engineer, Lower Mississippi Valley (ATTN: LMVED-G)
Division Engineer, Missouri River (ATTN: MRDED-G)
Division Engineer, New England (ATTN: NEDED-F)
Division Engineer, North Atlantic (ATTN: NADEN-TF)
Division Engineer, North Central (ATTN: NCDED-F)
Division Engineer, North Pacific (ATTN: NPDEN-GS)
Division Engineer, Ohio River (ATTN: ORDED-G)
Division Engineer, Pacific Ocean (ATTN: PODED-G)
Division Engineer, South Atlantic (ATTN: SADEN-F)
Division Engineer, South Pacific (ATTN: SPDED-G)
Division Engineer, Southwestern (ATTN: SWDED-F)

NEDED-F

14 July 1981

SUBJECT: Status of Seismic Evaluations and Analyses of Existing Dams

CDR USACE (DAEM-CWE-SS)
WASH DC 20314

1. Reference your letter of 11 June 1981, subject as above (copy attached) and to telephone discussions of 7 and 8 July 1981 with Mr. A. Walz.
2. Starting in September 1977, NED has been executing a program of seismic evaluations of its existing dams. Of the thirty-nine existing NED dams, thirty-five have been considered, the other four dams were excluded because their failures would not endanger lives or vital installations. The attached Table I is a listing of the dams covered by this program which includes purpose, type and peak accelerations for the design earthquakes for each site and a listing of the excluded dams.
3. Regional and detailed tectonic investigations have been completed for all thirty-five dams. The peak accelerations shown on Table I are based on the historical earthquake activity. All thirty-five dams have been analyzed for seismic stability by the pseudo-static method. Results of the analyses show factors of safety of unity, or greater, for the seismic coefficients for the seismic risk zones in which the dams are located and for the next higher zones. Reports covering these investigations and analyses were forwarded on 14 January 1981.
4. Six dams were investigated for their potential for liquefaction and cyclic mobility. The Phase I and Phase II reports for this investigation were forwarded on 14 January 1981 and 19 March 1981 respectively. Based on the results of this investigation, three dams have been selected for dynamic analysis for stability and deformation under earthquake loading. The dynamic analysis investigation is in progress for one dam, Knightville, and is planned for Surry Mountain and West Thompson starting in FY-82 and 83 respectively.

NEDED-F

13 July 1981

SUBJECT: Status of Seismic Evaluations and Analyses of Existing Dams

5. The attached Table II presents the status of NED activities for this program including start and completion dates and a funding summary.

FOR THE COMMANDER:

3 Inclosures

as

CF

Proj. Mgt. Br. (Mr. Gould)

Operations Div. (Mr. Minor)

GEB Files

Eng Div Files (1125)

JOE B. FRYAR, P. E.

Chief, Engineering Division

TABLE IEXISTING NED DAMS INVESTIGATED UNDER ER 1110-2-1806(EARTHQUAKE DESIGN AND ANALYSIS FOR CORPS OF ENGINEERS DAMS)JULY 1981

<u>DAM</u>	<u>PURPOSE</u>	<u>TYPE</u>	<u>PEAK ACCELERATION*(g)</u>
1. Ball Mountain	FC	E-R	0.18
2. Barre Falls	FC	E-R	0.18
3. Birch Hill	FC	E	0.18
4. Black Rock	FC	E	0.25
5. Blackwater	FC	E-R	0.18
6. Buffumville	FC	E	0.18
7. Colebrook River	FC-WS-R	E-R	0.25
8. Conant Brook	FC	E-R	0.18
9. East Branch	FC	E	0.18
10. East Brimfield	FC-R	E	0.25
11. Edward MacDowell	FC	E-R	0.18
12. Everett	FC-R	E-R	0.18
13. Franklin Falls	FC	E-R	0.25
14. Hall Meadow Brook	FC	E	0.18
15. Hancock Brook	FC	E	0.25
16. Hodges Village	FC-R	E-R	0.18
17. Hop Brook	FC-R	E	0.25
18. Hopkinton	FC-R	E-R	0.18
19. Knightville	FC	E	0.18
20. Littleville	FC-WS	E-R	0.18
21. Mad River	FC	E	0.18
22. Mansfield Hollow	FC	E	0.25
23. Northfield Brook	FC-R	E-R	0.25

<u>DAM</u>	<u>PURPOSE</u>	<u>TYPE</u>	<u>PEAK ACCELERATION*(g)</u>
24. North Hartland	FC-R	E	0.18
25. North Springfield	FC-R	E-R	0.18
26. Otter Brook	FC-R	E	0.18
27. Sucker Brook	FC	E-R	0.18
28. Surry Mountain	FC-R	E-R	0.13
29. Thomaston	FC	E-R	0.13
30. Townshend	FC-R	E	0.18
31. Tully Lake	FC	E-R	0.18
32. Union Village	FC	E-R	0.18
33. West Hill	FC-R	E	0.18
34. West Thompson	FC-R	E	0.18
35. Westville	FC-R	E	0.18

*Peak acceleration at site for design earthquake

LEGEND

FC - Flood Control
 WS - Water Supply
 R - Recreation
 E - Earth Fill
 R - Rock Fill

Existing NED Dams not included in program because failure would not endanger lives or vital installations.

- a. Charles River - Run-of-river dam to control fresh water level in tidal basin.
- b. Cherryfield - Log-crib run-of-river dam for ice jam control.
- c. Wright Reservoir - Low level dam (17-foot) for urban drainage system.
- d. Smelt Brook - Low level dam (15-foot) for urban drainage system.

TABLE II
STATUS OF SEISMIC EVALUATIONS AND ANALYSES OF NED DAMS
JULY 1981

Activity	Dams Covered	Dates		Funding Status (Thousand Dollars)	Report Titles
		Start	Complete		
1. Regional Tectonic Investigation	35 dams (See Table I)	Sep 77	Oct 78	19.2	*Remote Sensing Analysis of Fault Related Structures in New England and Related Seismic Hazards at Corps of Engineers Projects
2. Detailed Tectonic Investigation	35 dams (See Table I)	Jan 78	Sep 80	32.8	*Low-Sun Angle Aerial Reconnaissance of Faults and Lineaments of Southern New England
3. Pseudo-static Stability Analysis	35 dams (See Table I)	Jan 80	Oct 80	77.5	*Stability Analyses by the Seismic Coefficient Method-Completed New England Div. Dams
4. Liquefaction and Cyclic Mobility Investigation	Franklin Falls Surry Mountain Knightville Hodges Village West Thompson Mansfield Hollow	Jan 80	Jan 81	180.5	*a. Liquefaction and Cyclic Mobility Potential - COE Completed New England Dams - Phase I Investigations **b. " Phase II Investigations
5. Dynamic Analyses	a. Knightville b. Surry Mountain c. West Thompson	Mar 81 FY-82 FY-83	Dec 82(est) FY-83 FY-84	36.6(exp) 377.4 (budgeted) 344.0 (budgeted) 360.0 (budgeted)	

Total Expended	346.6
Budgeted	<u>1,081.4</u>
Grand Total	1,428.0

Copies furnished DAEN-CWE-SS by ltr of 14 Jan 81
* Copy furnished DAEN-CWE-SS by ltr of 19 Mar 81

EXHIBIT B

EXHIBIT B

SUMMARY OF EMBANKMENT AND FOUNDATION CONDITIONS*

TABLE OF CONTENTS

<u>SUBJECT</u>	<u>PAGE</u>
1. General Description	B-1
2. Geology	B-1
3. Foundation Condition	B-1
4. Triaxial Tests on Foundation Soils	B-3
5. Dam Embankment	B-4
6. Conclusions and Recommendations	B-5

PLATES

Project Location and Index	B-6
Embankment Details	B-7
Plan of Past Subsurface Exploration	B-8
Past Subsurface Exploration Records	B-9
Geologic Section	B-12
Geologic Sections and Test Data	B-13

*The material in this exhibit was obtained from the report entitled "Liquefaction and Cyclic Mobility Potential, Corps of Engineers Completed New England Dams, Phase I and II Investigation, Sept 1980 and Feb 1981 respectively.

SURRY MOUNTAIN DAM

1. GENERAL

The Surry Mountain Dam is located on the Ashuelot River, a tributary of the Connecticut River, about five miles northwest of Keene, New Hampshire (see Page B-6). The dam is one of a series included in the "Revised 1936 Flood Control Act Project for the Connecticut River Valley," and was constructed in 1939 and 1941.

The dam is a rolled-earth fill structure having a maximum height of 86 feet and a total length of approximately 1,800 feet. As shown on Page B-7 the embankment consists of a "select impervious" core that is tied to the foundation with a cutoff trench, and "random impervious" and "pervious" shells. Upstream and downstream slopes are riprapped with dumped rock, and vary in slope from 2.5 horizontal (H) to 1 vertical (V) between Elevation 565 feet and Elevation 550 feet, to 3H to 1V between Elevation 550 feet and Elevation 520 feet, to 5H to 1V below Elevation 520 feet. Rock toes exist on each slope. The outlet works and the main spillway weir are constructed on rock in the right (west) abutment.

2. GEOLOGY

The Ashuelot River is situated in a rugged upland area composed of igneous and closely folded metamorphic rocks, which at some locations occur at the surface due to weathering and pre-glacial stream erosion and at other locations are covered by glacial deposits. Igneous rock or granite is exposed near the right abutment of the dam, but as much as 100 feet of glacial overburden remains in the middle of the valley and near the left abutment.

Three types of glacial sediments comprise the overburden: (1) stratified outwash sand and gravel, (2) unstratified glacial till, and (3) uniform glacial lake deposits. These deposits are described in the next section in more detail, especially the glacial lake deposits which are felt to be the least resistant to liquefaction and cyclic mobility. The interstratified deposits of finely textured sand and silt are predominant in the foundation of the dam.

The lower part of the valley consists primarily of deposits of outwash sand and gravel. These deposits occur in partially eroded terrace formations, and are coarsely granular and pervious. Glacial till occurs in most of the hillside that forms the left abutment. This formation is well graded, devoid of bedding and very compact, making it relatively impervious.

3. FOUNDATION CONDITIONS

Previous Exploration. Prior to construction of the dam, subsurface exploration programs were conducted using core borings, test pits and auger borings. Fifty-eight core borings were advanced to explore a total of approximately 3,200 feet of subsurface material, including more than 300 feet of rock core and more than 340 feet of undisturbed soil samples. A total of twenty-four test pits

were dug in the area of the foundation and 124 in borrow areas; 128 auger borings were also used to explore both foundation and borrow areas. Boring locations are shown on Page B-8 and boring logs are shown on Pages B-9 thru B-11. Note that no penetration resistance was measured while advancing spoon samplers, and therefore, no quantitative description of density (such as SPT resistance) is provided on the boring logs.

The exploration program permitted cross-sections of subsoils to be developed as shown on pages B-12 and B-13. Page B-13 indicates that the foundation soils along the centerline of the dam are primarily interbedded sands and silts that extend to a maximum depth of approximately 100 feet. The Providence District system of soil classification was used. This system, summarized on Page B-13 classifies soils from Class I (clean gravel) to Class 13C(variable clay). It is important to note that soils designated by even numbers are uniformly graded, while those designated by odd numbers are well graded. Accordingly, Class 6 material (uniform fine sand to coarse silt) for example, might be expected to exhibit quite different liquefaction potential or cyclic mobility than Class 7 material (variable graded from gravel to coarse silt).

It may be seen from Page B-12 and B-13 that the shallow overburden in the right abutment consists of uniform fine sand and glacial silt (Classes 6, 8, 10 and 12) overlain by sand and gravel (Classes 2, 4, 5 and 7). The left abutment contains unstratified, dense glacial till consisting primarily of Classes 7, 9 and 11. However, the foundation of the embankment is composed of thick deposits of finely laminated and interstratified sediments designated as Classes 8 and 10, which are overlain and underlain by sands (often Class 6) and gravels.

It may be seen from the laboratory test data furnished on Page B-13 that void ratios for Class 10 material (uniform medium to fine silt) range from approximately 0.63 to 1.04, mean value being approximately 0.85. These void ratios presented for Class 8 material range from 0.61 to 0.76, which are also rather large. Accordingly, Class 10 soils would appear to exist at a relative density not much higher than 40 percent.

The low density of these soils is also indicated by low strengths. The angle of internal friction for the silt varies from approximately 23 to 34 degrees and the cohesion is negligible (less than 10 percent of the soil is clay). Low strength and the possibility of large plastic deformation or flow of the silts within the foundation soils was a concern of the designers with regard to stability, and led to the determination of consolidation characteristics of the material. It was decided to extend the duration of embankment construction to nearly two years to permit the weaker foundation soils to strengthen gradually through consolidation; also, the slopes were flattened to 5 horizontal to 1 vertical in the lower third of the embankment, presumable to provide both additional confining pressure and reduction of shear stress on the foundations.

Recent Borings. Two borings (SM-1 and SM-2) were made at the downstream toe of the dam to investigate the loose foundation soils. These borings were taken through the spoil fill beyond the rock toe. Boring SM-1 was taken to refusal at a depth of 83 feet and Boring SM-2 was taken to 80.5 feet. Standard penetration tests (SPT) were taken at 5-foot intervals except in the loose zone where undisturbed samples were taken in SM-1. In SM-1 between 26 and 55 feet, four 3 inch undisturbed Shelby tube samples were taken. In this zone, SPT's were taken at approximately 10 foot intervals.

Borings SM-1 and SM-2 indicate that there are approximately 50 feet of very loose to loose, stratified uniform very fine sand and silt with occasional thin, stiff silty clay layers. The upper portion is somewhat finer than the lower portion of the stratum. Laboratory gradation and water content tests* were performed on selected representative samples in the stratum. Based on water content and specific gravity determinations, the void ratios of the silt and fine sand are between 0.9 and 1.2. The sand below about 50 feet has void ratios in the range of 0.4 to 0.7. SPT values* in the silt and fine sand stratum were generally between 2 and 10 blows per foot. Below the stratum is about 20 feet of medium dense, stratified fine sand and gravelly sand. SPT values were generally between 15 to 20 blows per foot in this lower stratum.

4. TRIAXIAL TESTS ON FOUNDATION SOILS

Because void ratios were found to be large and SPT resistance low, it was considered advisable to conduct both undrained monotonic and cyclic tests on saturated samples of the foundation soils. The stress-controlled monotonic tests would indicate whether these soils exhibited dilative or contractive behavior when sheared, and hence whether a flow condition could occur in situ. The cyclic triaxial tests would indicate the extent of cyclic mobility that might be anticipated under the imposition of seismically induced shear stresses. Tests conducted on soils at Surry Mountain (three monotonic and two cyclic tests) were intended to be exploratory only. Conclusions based on results of these tests are therefore tentative, and should be based ultimately on more extensive laboratory test data.

Two monotonic stress controlled triaxial tests were conducted on specimens recovered from Sample T2 in Boring SM1 at a depth of approximately 36 feet. The two specimens comprised of fine sand with some silt had initial dry unit weights of 101.7 pcf and 97.8 pcf, respectively. The plots of deviator stress versus axial strain and pore pressure versus strain* showed marked dilation when sheared. Accordingly, the points shown on the plot of void ratio versus effective confining pressure will lie below the flow line (associated with actual liquefaction) for this soil. It should be noted that the densities of the soils tested may not be representative of most of the foundation soils, as the SPT resistance tended to be somewhat higher around the depth of 36 feet compared with that at lesser and greater depths. Moreover, the very loose silt stratum found to exist between depths of 12 feet and 27 feet is expected to contract (and thus flow) when sheared.

*Test results are shown in Exhibit C

A single monotonic triaxial test was conducted on a reconstituted specimen comprising of silt and fine sand at an initial dry density of 92.2 pcf. (The material tested was that used previously in cyclic tests conducted on undisturbed samples, as described below.) As shown on the plots of deviator stress versus strain and pore pressure versus strain*, this specimen exhibited contraction during shearing. Accordingly, it is likely that at least part of the silt stratum may exist at a void ratio greater than the critical value.

Two cyclic triaxial tests were conducted on undisturbed silt samples recovered in Sample T1 from Boring SM-1 at a depth of approximately 27 feet. The initial dry densities of the two specimens were 93.6 pcf and 91.2 pcf respectively. As shown on the plot of shear stress ratio versus number of cycles, the soil exhibited a large accumulation of pore pressure and 5 percent strain (peak-to-peak) in slightly more than one cycle for a stress ratio of 0.3, and 10 percent strain at three cycles. For a stress ratio of 0.2, 5 percent and 10 percent strains occurred at 12 cycles and 20 cycles, respectively. These low cyclic strengths further indicate the contractive nature of the silts encountered in the foundation soils.

5. DAM EMBANKMENT

The rolled-earth fill method, rather than a hydraulic fill method, was used for construction of the embankment, primarily to make a two season construction schedule economical. The foundation was expected to consolidate and strengthen sufficiently during construction to permit adequate stability against plastic flow.

The embankment materials were procured from local borrow areas and were placed by trucks or crawler wagons and compacted by sheepsfoot rollers. The embankment is composed of four types of fill:

- (1) pervious fill
- (2) impervious and random impervious fill
- (3) rock toes and dumped riprap
- (4) gravel filters and bedding

According to the design memorandum, the pervious fill was to consist of Classes 2, 3, 4 and 5 soils, and were to be placed in such a manner that the finer materials would be nearer the random impervious section; the coarser materials were to be placed nearer the outer faces of the embankment. The impervious material consists of Classes 7, 9 and 11. All soils were to be either dried or moistened to near optimal water content, spread in 6 inch thick layers, and rolled. Standard Proctor tests yielded moist weights of 120 to 140 pcf at optimal water contents of 9 to 16 percent for pervious materials; moist unit weights of 135-145 pcf were obtained at optimal water contents of 8 to 14 percent for impervious materials. The impervious section was to be compacted by a sheepsfoot roller, the random impervious sections by twin rollers, and the pervious sections by a plain cylindrical roller. A minimum of six passes of the rollers was specified.

*Test results are shown in Exhibit C

Material for rock toes and riprap were to be obtained primarily from structural excavations. The rock was to be dumped in place with the larger rocks at the outer faces and the smaller rocks and spalls adjacent to the embankment. Gravel bedding and select gravel filter material was to be inspected visually.


Stability analyses of the embankment itself yielded a factor of safety near 2.0 for the most severe loading conditions, i.e., sudden drawdown. Also, owing to the presence of the weaker foundation soils, a stability analysis against sliding was conducted, and yield a factor of safety of 1.87. This value is based on a conservative estimate of $\phi = 25$ degrees.

6. CONCLUSIONS AND RECOMMENDATIONS

The potentials for actual liquefaction and cyclic mobility of the embankment soils are expected to be "negligible," as these soils will dilate during shear. Although the embankment soils might exhibit cyclic mobility, the strains are expected to be small because of the high density of these materials and the relatively low (0.13g) peak ground acceleration.

Standard penetration resistances and the results of monotonic and cyclic triaxial tests of foundation sands and silts* indicate the presence of foundation soil zones with "possible" potential for liquefaction and a cyclic mobility potential of "high" at the embankment toes and "possible" at the embankment centerline. It is recommended that additional explorations and laboratory testing be conducted to better establish those soil properties related to liquefaction and cyclic mobility and the spatial distribution of those properties. It is also recommended that a dynamic analysis be performed which properly accounts for seismic loading and material properties.

*Test results are shown in Exhibit C



VICINITY MAP


SCALE 0 5 MILES

LEGEND

- HIGHWAYS
- RAILROADS
- ELECTRIC POWER LINE
- MAXIMUM RESERVOIR FLOW LINE
- ELECTRIC SUBSTATION
- HYDROELECTRIC GENERATING STATION

INDEX TO DRAWINGS

SHEET NO.	TITLE
1	PROJECT LOCATION AND INDEX
2	HYDROGRAPHIC
3	PLAN OF SUBSURFACE EXPLORATIONS NO. 1
4	PLAN OF SUBSURFACE EXPLORATIONS NO. 2
5	RECORD OF SUBSURFACE EXPLORATIONS NO. 1
6	RECORD OF SUBSURFACE EXPLORATIONS NO. 2
7	RECORD OF SUBSURFACE EXPLORATIONS NO. 3
8	WORK AREA
9	GENERAL PLAN
10	EMBANKMENT DETAILS NO. 1
11	EMBANKMENT DETAILS NO. 2
12	SPILLWAY-PLAN AND SECTIONS
13	SPILLWAY-APPROACH AND WEIR
14	RETAINING WALLS
15	OUTLET WORKS
16	ASSEMBLY-GATE SHAFT AND TUNNEL
17	INTAKE STRUCTURE DETAILS NO. 1
18	INTAKE STRUCTURE DETAILS NO. 2
19	OUTLET PORTAL
20	TUNNEL TRANSITION
21	GATE SHAFT AND BASEMENT
22	GATE SHAFT DETAILS
23	BASEMENT DETAILS
24	INTAKE STRUCTURE-STEEL REINFORCEMENT NO. 1
25	INTAKE STRUCTURE-STEEL REINFORCEMENT NO. 2
26	OUTLET PORTAL AND SPILLWAY STRUCTURES-STEEL REINFORCEMENT
27	TUNNEL TRANSITION-STEEL REINFORCEMENT NO. 1
28	TUNNEL TRANSITION-STEEL REINFORCEMENT NO. 2
29	GATE SHAFT AND BASEMENT-STEEL REINFORCEMENT NO. 1
30	GATE SHAFT AND BASEMENT-STEEL REINFORCEMENT NO. 2
31	BASEMENT-STEEL REINFORCEMENT NO. 1
32	BASEMENT-STEEL REINFORCEMENT NO. 2
33	STEEL REINFORCEMENT-BAR SCHEDULE NO. 1
34	STEEL REINFORCEMENT-BAR SCHEDULE NO. 2
35	STEEL REINFORCEMENT-BAR SCHEDULE NO. 3
36	STEEL REINFORCEMENT-BAR SCHEDULE NO. 4
37	GATES AND ACCESSORIES-GENERAL ARRANGEMENT NO. 1
38	GATES AND ACCESSORIES-GENERAL ARRANGEMENT NO. 2
39	GATES AND ACCESSORIES-CONDUIT LINING NO. 1
40	GATES AND ACCESSORIES-CONDUIT LINING NO. 2
41	MISCELLANEOUS METAL DETAILS NO. 1
42	MISCELLANEOUS METAL DETAILS NO. 2
43	MISCELLANEOUS METAL DETAILS NO. 3
44	MISCELLANEOUS METAL DETAILS NO. 4
45	OPERATING HOUSE-ELEVATIONS
46	OPERATING HOUSE-DETAILS NO. 1
47	OPERATING HOUSE-DETAILS NO. 2
48	OPERATING HOUSE-STRUCTURAL STEEL
49	ELECTRIC LIGHT AND POWER SYSTEM
50	GAGES-TILE AND STAFF
51	ACCESS ROAD
52	ACCESS BRIDGE-SUBSTRUCTURE
53	ACCESS BRIDGE-SUPERSTRUCTURE NO. 1
54	ACCESS BRIDGE-SUPERSTRUCTURE NO. 2
55	FIELD OFFICE
56	ACCESS ROAD-WING WALL AND TOE WALL
57	ACCESS ROAD-EAST ABUTMENT



LOCATION MAP

SCALE 0 20 MILES

LEGEND

- HIGHWAYS
- RAILROADS

CONNECTICUT RIVER FLOOD CONTROL

SURRY MOUNTAIN DAM


PROJECT LOCATION AND INDEX

ASHUELOT RIVER, NEW HAMPSHIRE
IN 37 SHEETS SCALE AS SHOWN SHEET NO. 1

U.S. ENGINEER OFFICE, PROVIDENCE, R.I. DEC. 1938

SUBMITTED: J. D. Brown
 APPROVAL: [Signature]
 RECOMMENDED: [Signature]
 APPROVED: [Signature]
 PRINCIPAL ENGINEER: [Signature]
 CHIEF ENGINEERING SECTION: [Signature]
 DESIGNED: [Signature]
 TRACED BY: [Signature]
 CHECKED BY: [Signature]
 FILE NO. CT-1-1-1-1-1

1520	Sheet No. 37 added to set	10/1/39	289
1521	Sheet No. 35 added to set	10/1/39	289
1522	Sheet No. 35 added to set	10/1/39	289
1523	Field Office drawing omitted	10/1/39	289
1524	Field Office drawing omitted	10/1/39	289
1525	Field Office drawing omitted	10/1/39	289
1526	Field Office drawing omitted	10/1/39	289
1527	Field Office drawing omitted	10/1/39	289
1528	Field Office drawing omitted	10/1/39	289
1529	Field Office drawing omitted	10/1/39	289
1530	Field Office drawing omitted	10/1/39	289
1531	Field Office drawing omitted	10/1/39	289
1532	Field Office drawing omitted	10/1/39	289
1533	Field Office drawing omitted	10/1/39	289
1534	Field Office drawing omitted	10/1/39	289
1535	Field Office drawing omitted	10/1/39	289
1536	Field Office drawing omitted	10/1/39	289
1537	Field Office drawing omitted	10/1/39	289
1538	Field Office drawing omitted	10/1/39	289
1539	Field Office drawing omitted	10/1/39	289
1540	Field Office drawing omitted	10/1/39	289
1541	Field Office drawing omitted	10/1/39	289
1542	Field Office drawing omitted	10/1/39	289
1543	Field Office drawing omitted	10/1/39	289
1544	Field Office drawing omitted	10/1/39	289
1545	Field Office drawing omitted	10/1/39	289
1546	Field Office drawing omitted	10/1/39	289
1547	Field Office drawing omitted	10/1/39	289
1548	Field Office drawing omitted	10/1/39	289
1549	Field Office drawing omitted	10/1/39	289
1550	Field Office drawing omitted	10/1/39	289
1551	Field Office drawing omitted	10/1/39	289
1552	Field Office drawing omitted	10/1/39	289
1553	Field Office drawing omitted	10/1/39	289
1554	Field Office drawing omitted	10/1/39	289
1555	Field Office drawing omitted	10/1/39	289
1556	Field Office drawing omitted	10/1/39	289
1557	Field Office drawing omitted	10/1/39	289
1558	Field Office drawing omitted	10/1/39	289
1559	Field Office drawing omitted	10/1/39	289
1560	Field Office drawing omitted	10/1/39	289
1561	Field Office drawing omitted	10/1/39	289
1562	Field Office drawing omitted	10/1/39	289
1563	Field Office drawing omitted	10/1/39	289
1564	Field Office drawing omitted	10/1/39	289
1565	Field Office drawing omitted	10/1/39	289
1566	Field Office drawing omitted	10/1/39	289
1567	Field Office drawing omitted	10/1/39	289
1568	Field Office drawing omitted	10/1/39	289
1569	Field Office drawing omitted	10/1/39	289
1570	Field Office drawing omitted	10/1/39	289
1571	Field Office drawing omitted	10/1/39	289
1572	Field Office drawing omitted	10/1/39	289
1573	Field Office drawing omitted	10/1/39	289
1574	Field Office drawing omitted	10/1/39	289
1575	Field Office drawing omitted	10/1/39	289
1576	Field Office drawing omitted	10/1/39	289
1577	Field Office drawing omitted	10/1/39	289
1578	Field Office drawing omitted	10/1/39	289
1579	Field Office drawing omitted	10/1/39	289
1580	Field Office drawing omitted	10/1/39	289
1581	Field Office drawing omitted	10/1/39	289
1582	Field Office drawing omitted	10/1/39	289
1583	Field Office drawing omitted	10/1/39	289
1584	Field Office drawing omitted	10/1/39	289
1585	Field Office drawing omitted	10/1/39	289
1586	Field Office drawing omitted	10/1/39	289
1587	Field Office drawing omitted	10/1/39	289
1588	Field Office drawing omitted	10/1/39	289
1589	Field Office drawing omitted	10/1/39	289
1590	Field Office drawing omitted	10/1/39	289
1591	Field Office drawing omitted	10/1/39	289
1592	Field Office drawing omitted	10/1/39	289
1593	Field Office drawing omitted	10/1/39	289
1594	Field Office drawing omitted	10/1/39	289
1595	Field Office drawing omitted	10/1/39	289
1596	Field Office drawing omitted	10/1/39	289
1597	Field Office drawing omitted	10/1/39	289
1598	Field Office drawing omitted	10/1/39	289
1599	Field Office drawing omitted	10/1/39	289
1600	Field Office drawing omitted	10/1/39	289



NOTES

The bottom of the cut-off trench indicates the approximate limit of excavation and backfill, and may be raised or lowered depending on actual conditions as disclosed in the field.

Elevations refer to Mean Sea Level Datum.

Sections are taken at right angles to Stations as the centerline of the dam.


See Sheet No. 11 for additional details of embankment.

Figures in hexagons indicate bid item numbers under which payment made.

The indicated line of separation between the select impervious and random impervious fill in the embankment, will be variable; the line between the random impervious and pervious fill shall be adhered to.

Both upstream and downstream slopes change from 1 on 2 1/2 to 1 on 3 at Elev. 520.5 and also from 1 on 2 1/2 to 1 on 3 at Elev. 520.0.

CONNECTICUT	RIVER	FLOOD	CONTROL
<p align="center">SURRY MOUNTAIN DAM EMBANKMENT DETAILS NO. 1</p>			
ASHLEYOT RIVER,		NEW HAMPSHIRE	
IN SIX SHEETS		SCALE	SHEET NO. 10
AS SHOWN			
U.S. ENGINEER OFFICE, PROVIDENCE, R.I., DEC. 1934			
DESIGNED BY <i>J. S. Gorman</i>	APPROVED BY <i>E. J. [Signature]</i>	CHECKED BY <i>[Signature]</i>	DATE DEC. 1934
DRAWN BY CHECKED BY FILE NO.			



LEGEND

- ⊙ Core location (BH)
- Existing roads
- Boundary of structure and excavations
- ⊞ Dam structure
- ⊞ Dam test pit


NOTES

For record of bore holes see Sheets No. 1 and 6.
Large borings and shallow test pits are shown.
Subsurface investigations by means of core borings,
large borings and test pits have been made at the sites
of the dam and approaches the logs and samples
pertaining to these investigations may be inspected at
the United States Engineer Office at Providence, Rhode
Island.
Contours interval 5 feet.
All positions refer to Mean Sea Level Datum.


EXPLANATION OF SECTION DESIGNATION

The section designations used are designated by
fractions, the numerator of which is the section
reference and the denominator the sheet number
on which the section is taken or shown.
Example: Section 1 is taken on Sheet No. 1
and the section is actually shown on Sheet No. 2.
On Sheet No. 3 the section reference would be
noted 1/3 and on Sheet No. 4 the section would
be noted 1/4.


CONNECTICUT RIVER FLOOD CONTROL	
SURRY MOUNTAIN DAM	
PLAN OF SUBSURFACE EXPLORATION-NO. 1	
ASHUELOT RIVER	NEW HAMPSHIRE
1927 SHEET 15	SHEET NO. 1
U. S. ENGINEER OFFICE, PROVIDENCE, R. I., DEC. 1938	
<div style="display: flex; justify-content: space-between;"> <div> <p><i>J. D. [Signature]</i></p> <p>Chief Engineer</p> </div> <div> <p><i>[Signature]</i></p> <p>Assistant Engineer</p> </div> </div>	
FILE NO. CT-1-101	



CONNECTICUT RIVER FLOOD CONTROL	
SURRY MOUNTAIN DAM	
RECORD OF	
SUBSURFACE EXPLORATION-NO. 1	
ASHLEY RIVER	NEW HAMPSHIRE
IN 57 SHEETS	SCALE AS SHOWN SHEET NO. 9
U. S. ENGINEER OFFICE, PROVIDENCE, R. I. DEC 1938	
SUPERVISOR: <i>[Signature]</i> CHECKED: <i>[Signature]</i> DRAWN: <i>[Signature]</i> FILE NO. 61-1-1-53	




FOUNDATION EXPLORATIONS



BORROW AREA EXPLORATIONS

LEGEND








KEY TO DESCRIPTIONS

MODIFYING TERM	VALUE
And	40% to 50%
Some	20% to 40%
Little	5% to 20%
Trace	5% or less
Water table indicated thus	W.T.

NOTES

For general notes applying to this sheet, see Sheet No. 1.
For location of Foundation Explorations, see Sheet No. 1.
For location of Borrow Area Explorations, see Sheet No. 1.
B.H. = Core Boring
B.A. = Auger Boring
F.T. = Test Pit

CONNECTICUT RIVER FLOOD CONTROL			
SUNNY MOUNTAIN DAM			
RECORD OF			
SUBSURFACE EXPLORATION-NO. 2			
ASHUELOT RIVER, NEW HAMPSHIRE		SCALE: AS SHOWN	
NO. 57 SHEETS		SHEET NO. 2	
U.S. ENGINEER OFFICE, PROVIDENCE, R.I., DEC. 1938			
SUBMITTED: J. J. Quinn		APPROVED: R. J. Quinn	
DESIGNED: J. J. Quinn		CHECKED: R. J. Quinn	
DRAWN: J. J. Quinn		FILE NO. 07-1-1184	



LEGEND

- Sand
- Silt or Rock floor
- Clay
- Granite
- Gravel
- Blocky or Fractured Granite




NOTES

For location of profiles and sections see Sheet No. 3.
For location of bore holes see Sheet No. 3.
For logs of bore holes see Sheets No. 5 and 6.
Elevation refers to Mean Sea Level Datum.
Center lines of graphic logs coincide with those of bore holes.

CONNECTICUT RIVER FLOOD CONTROL	
SURREY MOUNTAIN DAM	
RECORD OF	
SUBSURFACE EXPLORATION-NO. 3	
ASHUELOT RIVER,	NEW HAMPSHIRE
IN 57 SHEETS	SHEET NO. 7
U. S. ENGINEER OFFICE, PROVIDENCE, R. I., DEC. 1938	
SUBMITTED	APPROVED
CHIEF ENGINEER	CHIEF OF ENGINEERS
CHIEF ENGINEERING SECTION	CHIEF OF ENGINEERS
COMPILED	FILE NO. EY-1-1165


KEY	DATE	REVISION	INDICATED BY	REV. BY	CHK. BY	APP. BY
1-4-41		1-4-41				

R-12



NOTES
Elevations refer to Mean Sea Level Datum.
Numbers in Legend refer to Soil Classes
adopted by Providence District.


Sticky condition in granite
Granite




LEGEND

- | | |
|--|--|
| 1 Clean Gravel Contains little coarse to medium sand. | 2 Uniform Coarse to Medium Sand. Contains little gravel and fine sand. |
| 3 Variable - Graded from Gravel to Medium Sand. Contains little fine sand. | 4 Uniform Medium to Fine Sand. Contains little coarse sand and coarse silt. |
| 5 Variable - Graded from Gravel to Fine Sand. Contains little coarse silt. | 6 Uniform Fine Sand to Coarse Silt. Contains little medium sand and medium silt. |
| 7 Variable - Graded from Gravel to Coarse Silt. Contains little medium silt. | 8 Uniform Coarse to Medium Silt. Contains little fine sand and fine silt. |
| 9 Variable - Graded from Gravel to Medium Silt. Contains little fine silt. | 10 Uniform Medium to Fine Silt. Contains little coarse silt and coarse clay. Possesses behavior characteristics of silt. |
| 11 Variable - Graded from Gravel or Coarse Sand to Fine Silt. Contains little coarse clay. | 12 Uniform Medium Silt to Coarse Clay. Contains little coarse silt and medium clay. Possesses behavior characteristics of clay. |
| 13 Variable - Graded from Coarse Sand to Clay. Contains little fine clay (silt). Possesses behavior characteristics of silt. | 14 Uniform Fine Silt to Medium Clay. Contains little medium silt and fine clay (silt). Possesses behavior characteristics of silt. |
| 15 Variable Clay Graded from Sand to Fine Clay (silt). Possesses behavior characteristics of clay. | 16 Uniform Clay. Contains little silt. Possesses behavior characteristics of clay. |

CONNECTICUT RIVER FLOOD CONTROL	
SURREY MOUNTAIN DAM	
GEOLOGIC SECTIONS	
ASHKELOT RIVER	NEW HAMPSHIRE
11 SHEETS	AS SHOWN
U.S. ENGINEER OFFICE, PROVIDENCE, R.I.	
MAY 1938	
DESIGNED BY	FILE NO.
DRAWN BY	FILE NO.
CHECKED BY	FILE NO.
DATE	REVISION
REVISION	REVISION






TABLE

RELATIVE PERMEABILITIES	
Class of Material	Coefficient of Permeability
1	100 to 500
2	20 to 100
3	5 to 20
4	1 to 5
5	0.1 to 1.0
6	Greater than 1000
7	200 to 1000
8	50 to 200
9	15 to 50
10	3 to 15
11	0.2 to 3.0

NOTE
To convert coefficient to feet per minute, multiply by 2



CONNECTICUT RIVER FLOOD CONTROL
SURREY MOUNTAIN DAM
GEOLOGIC SECTIONS
AND TEST DATA

ASHUELOT RIVER NEW HAMPSHIRE

IN 3 SHEETS SCALE SHEET NO. 2
HORIZONTAL 1 IN. = 50 FT. VERTICAL 1 IN. = 10 FT.

U.S. ENGINEER OFFICE, PROVIDENCE, R.I. MAY, 1938

DESIGNED BY [Signature] CHECKED BY [Signature] APPROVED BY [Signature]
PRINCIPAL ENGINEER CHIEF ENGINEER SECTION CHIEF FLOOD CONTROL DIVISION DISTRICT ENGINEER


COMPILED BY [Signature] DRAWN BY [Signature] FILE NO. [Signature]
CHECKED BY [Signature] TRACKED BY [Signature] CHECKED BY [Signature]

EXHIBIT C

BORING LOGS AND LABORATORY TEST RESULTS*

<u>SUBJECT</u>	<u>PAGE</u>
Boring Location Plan	C-1
Boring No. SM-1	C-2
Boring No. SM-2	C-5
Laboratory Test Results	C-8
Laboratory Testing Data Summary	C-9
Monotonic Triaxial Test Results	C-12
Cyclic Triaxial Test Results	C-18
Gradation Test Results	C-19

*The material in this Exhibit was obtained from report entitled
"Liquefaction and Cyclic Mobility Potential, Corps of Engineers
Completed New England Dams, Phase II - Investigation, February 1981.



BORING CO. D'Appolonia Drilling
FOREMAN Steve Brilmyer
G-Z-D ENGINEER T. vonRosenvinge

BORING LOCATION STA. 11+10 (See Plan)
GROUND ELEV. 489.5'+ M.S.L.
DATE START 10/1/80 DATE END 10/3/80

CASING

SIZE: 4" O.D.
HAMMER: N/A lb.
FALL: N/A

SAMPLER

TYPE: 2" O.D. Split Spoon OTHER: 3" Shelby Tube
HAMMER 140 lb. W/ Check Valve
FALL: 30"

GROUNDWATER READINGS

DATE	DEPTH	CASING AT	STABILIZATION TIME
10/1	4.5'	8'	10 minutes

DEPTH	CAS. BL. /FT.	SAMPLE				STRATA CHG. and GEN. DESC.	SAMPLE DESCRIPTION	NOTE
		NO.	PEN./REC.	DEPTH	BLOWS/6"			
5						FILL 5'	Loose, gray-brown, fine SAND, some (+) slightly Organic Silt, trace of roots (SM) and (OL)	
		S-1	18"/12"	3.5'-5.0'	1-1-3			
10						GRANULAR FILL 12.5'	Medium dense, brown-gray, fine to coarse SAND, some (-) fine to coarse Gravel, trace (+) Silt, slight organic odor (SW-SM)	
		S-2	18"/8"	8.5'-10.0'	6-7-5			
15						STRATIFIED SILT AND CLAY	Loose, gray, SILT, little fine Sand (ML)	1
		S-3	18"/10"	13.5'-15.0'	2-1-2			
20							Very soft, gray, interbedded SILT and CLAY, trace fine Sand, low to medium plasticity (CL)	
		S-4	18"/18"	18.5'-20.0'	1-1-1			
25							Loose, gray SILT and fine SAND (ML)	
		T-1	24"/24"	26'-28'	Push			
30						STRATIFIED FINE SAND AND SILT	Loose, gray, fine SAND, trace Silt (SP-SM)	
		S-5	18"/10"	30'-31.5'	2-2-2			

REMARKS: 1. Hollow stem augering to 15' replaced with 4" O.D. casing to 15' depth, and used bentonite drilling mud beyond this depth.

NOTES: 1) THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY BETWEEN SOIL TYPES AND THE TRANSITION MAY BE GRADUAL.
2) WATER LEVEL READINGS HAVE BEEN MADE IN THE DRILL HOLES AT TIMES AND UNDER CONDITIONS STATED ON THE BORING LOGS. FLUCTUATIONS IN THE LEVEL OF THE GROUNDWATER MAY OCCUR DUE TO OTHER FACTORS THAN THOSE PRESENT AT THE TIME MEASUREMENTS WERE MADE.

DEPTH	CAS. BL. /FT.	SAMPLE				STRATA CHNG and GEN. DESC.	SAMPLE DESCRIPTION	NOTE
		NO.	PEN./REC.	DEPTH	BLOWS/6"			
35		T-2	24"/20"	35'-37'	Push	STRATI- FIED FINE SAND AND SILT	Gray fine SAND, some Silt (SM)	
40		S-6	18"/10"	40'- 41.5'	4-5-4		Loose, gray, fine SAND, little (-) Silt (SP-SM)	
		T-3	24"/24"	43'-45'	Push			
45								
		S-7	18"/12"	48'- 49.5'	3-3-3		Loose, gray, SILT and fine SAND, (ML)	
50								
						61.5'		
		T-4	24"/22"	53'-55'	Push			
55								
		S-8	18"/8"	58'- 59.5'	4-2-6		Loose, gray, fine SAND, little (+) medium Sand layers (1" thick), little Silt, trace Clay layers (1/8" thick) (SP-SM)	
60								
		S-9	18"/12"	63'- 64.5'	10-9-8		Medium dense, gray, fine to coarse SAND, trace (+) Silt (SW-SM)	
65								
						STRATI- FIED SAND		
		S-10	18"/12"	68'- 69.5'	5-7-8		Medium dense, gray, fine SAND, trace Silt, trace (-) fine Gravel (SP-SM)	
70								

REMARKS:

NOTES: 1) THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY BETWEEN SOIL TYPES AND THE TRANSITION MAY BE GRADUAL.
2) WATER LEVEL READINGS HAVE BEEN MADE IN THE DRILL HOLES AT TIMES AND UNDER CONDITIONS STATED ON THE BORING LOGS. FLUCTUATIONS IN THE LEVEL OF THE GROUNDWATER MAY OCCUR DUE TO OTHER FACTORS THAN THOSE PRESENT AT THE TIME MEASUREMENTS WERE MADE.

C-4

GOLDBERG, ZOINO, DUNNICLIFF &
ASSOCIATES, INC.
GEOTECHNICAL CONSULTANTS

PROJECT
SURRY MOUNTAIN DAM
KEENE, NEW HAMPSHIRE

REPORT OF BORING NO. SM-2
SHEET 1 OF 3
DATE 10/3/80 FILE G-2729

BORING CO. D'Appolonia Drilling
FOREMAN Steve Brilmyer
G-Z-D ENGINEER T. vonRosenvinge

BORING LOCATION STA. 12+73 (See Plan)
GROUND ELEV. 490.5'± M.S.L.
DATE START 10/3/80 DATE END 10/4/80

CASING SAMPLER
SIZE: 6" Hollow Stem Auger TYPE: 2" O.D. Split Spoon OTHER:
HAMMER: N/A lb. HAMMER 140 lb.
FALL: N/A FALL: 30"

GROUNDWATER READINGS			
DATE	DEPTH	CASING AT	STABILIZATION TIME
10/4	6.5'	15'	14 hours

DEPTH	CAS. BL. /FT.	SAMPLE				STRATA CHG. and GEN. DESC.	SAMPLE DESCRIPTION	NOTE
		NO.	PEN./REC.	DEPTH	BLOWS/6"			
5						GRANULAR FILL	Loose, brown, fine SAND, little (+) Silt, trace fine roots (moist fill) (SP-SM)	
		S-1	18"/18"	3.5'-	2-1-1			
				5.0'				
10		S-2	18"/6"	8.5'-	5-4-2		Loose, gray, fine to coarse SAND, some Gravel, trace Silt, trace organic odor (SW)	
				10.0'				
15		S-3	18"/14"	15'-	8-8-8		Medium dense, brown, fine (+) to coarse, micaceous SAND, some fine Gravel, trace (+) Silt (SW-SM)	
				16.5'				
20						STRATIFIED SAND, SILT, CLAY	Soft gray SILT, trace thin (1/8" - 1/4" thick) Clay layers, trace fine Sand (ML)	
		S-4	18"/18"	21'-	2-2-3			
				22.5'				
25		S-5	18"/12"	24.5'-	2-2-2		Soft, gray, SILT (ML) and Silty Clay (CL) (clay in layers ranging from 1/4" to 3" thick), trace fine Sand, slight plasticity	
				26'				
30		S-6	18"/12"	29'-	6-4-4		Loose, gray, SILT, little fine Sand layers, trace Stiff Clay layers (1/4" thick) (ML)	
				30.5'				

REMARKS:

NOTES: 1) THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY BETWEEN SOIL TYPES AND THE TRANSITION MAY BE GRADUAL.
2) WATER LEVEL READINGS HAVE BEEN MADE IN THE DRILL HOLES AT TIMES AND UNDER CONDITIONS STATED ON THE BORING LOGS. FLUCTUATIONS IN THE LEVEL OF THE GROUNDWATER MAY OCCUR DUE TO OTHER FACTORS THAN THOSE PRESENT AT THE TIME MEASUREMENTS WERE MADE.

DEPTH	CAS. BL. /FT.	SAMPLE				STRAT. CHNG and GEN. DESC.	SAMPLE DESCRIPTION	NOTE
		NO.	PEN./REC.	DEPTH	BLOWS/6"			
35		S-7	18"/16"	34.5'- 36'	2-3-5	STRATI- FIED SILT AND CLAY	Loose, gray, clayey SILT, slight plasticity (ML)	1
40		S-8	18"/11"	39.5'- 41'	6-4-4		Loose, gray, SILT, some fine Sand trace Stiff Clay (a 1" thick layer) (ML)	
45		S-9	18"/16"	44.5'- 46'	3-3-6	46'	Loose, gray SILT, little fine Sand, trace Clay layers (1/8" to 1/2" thick) (ML)	1
						FINE SAND		
50		S-10	18"/10"	49.5'- 51'	6-6-7		Medium dense, gray, fine SAND, little (-) Silt (SP-SM)	
55		S-11	18"/14"	54.5'- 56'	6-7-9		Medium dense, gray, fine SAND, trace Silt (SP-SM)	
60		S-12	18"/11"	59.5'- 61'	4-6-7	62'	Medium dense, gray, fine SAND, little medium Sand layers (1" thick) trace fine Gravel (SP)	
						STRATI- FIED SAND		
65		S-13	18"/6"	64'- 65.5'	12-8-9		Medium dense, gray, fine to coarse SAND, some fine Gravel, trace fine Sand layer (1/2" thick) trace Silt (SW-SM)	
70		S-14	18"/8"	69'- 70.5'	7-6-7		Medium dense, gray, fine to coarse SAND, little fine Gravel, trace Silt (SW-SM)	

REMARKS: 1. Some gravelly resistance encountered with the roller bit at 37' and from 62' to 64'.

NOTES: 1) THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY BETWEEN SOIL TYPES AND THE TRANSITION MAY BE GRADUAL.
2) WATER LEVEL READINGS HAVE BEEN MADE IN THE DRILL HOLES AT TIMES AND UNDER CONDITIONS STATED ON THE BORING LOGS. FLUCTUATIONS IN THE LEVEL OF THE GROUNDWATER MAY OCCUR DUE TO OTHER FACTORS THAN THOSE PRESENT AT THE TIME MEASUREMENTS WERE MADE.

REMARKS:

NOTES: 1) THE STRATIFICATION LINES REPRESENT THE APPROXIMATE BOUNDARY BETWEEN SOIL TYPES AND THE TRANSITION MAY BE GRADUAL.
2) WATER LEVEL READINGS HAVE BEEN MADE IN THE DRILL HOLES AT TIMES AND UNDER CONDITIONS STATED ON THE BORING LOGS. FLUCTUATIONS IN THE LEVEL OF THE GROUNDWATER MAY OCCUR DUE TO OTHER FACTORS THAN THOSE PRESENT AT THE TIME MEASUREMENTS WERE MADE.

LABORATORY TEST RESULTS

39

[illegible]


LABORATORY TESTING DATA SUMMARY

Boring No.	Sample No.	Depth ft.	Laboratory or Test No.	IDENTIFICATION TESTS							Permeability	STRENGTH TESTS					CONSOL. Cc / eo	Laboratory Log and Soil Description
				Water Content %	LL %	PL %	Sieve -200 %	Hyd -2μ %	G _s	Y _d pcf		Torvane or Type Test	σ _c or σ _c OR σ psi	Failure Criteria	σ ₁ - σ ₃ OR τ psi	Strain %		
SM1	S12	78.5-80.0	40	18.4														Grey fine to medium SAND, little fine Gravel, trace Silt (SM - SP)
SM2	S4	21.0-22.5	41	37.7														Grey SILT, trace fine Sand (ML)
SM2	S5	24.5-26.0	42	35.3	29	26	97	13										Grey Clayey SILT of slight plasticity. Trace fine Sand (ML)
SM2	S7	34.5-36.0	43	41.2	33	30	100	4										Grey Clayey SILT of slight plasticity (ML)
SM2	S9	44.5-46.0	44	35.4			88											Grey SILT, little fine Sand (ML)

LABORATORY TESTING DATA SUMMARY

[illegible]

6-11




TEST No.	SYM.	BORING No.	DEPTH (ft.)	INITIAL CONDITIONS			CONDITIONS BEFORE LOADING					FINAL CONDITIONS	
				w_n (%)	γ_d pcf	HT. DIA.	$\sigma_1 = \sigma_3$ psf	U_d psf	ϵ_v (%)	β (%)	θ %	w_n (%)	γ_d pcf
T54.3.1	△	SMI	35.9-36.4	22.2	101.7	6.000 2.870	4320	10080	1.07	95	0.65	23.4	102.8
T54.3.2	○	SMI	35.4-35.9	24.5	97.8	6.000 2.850	1440	7200	0.73	97	0.72	24.5	98.5


SURRY MOUNTAIN DAM
SURRY, N.H.

SUMMARY PLOT
MONOTONIC TRIAXIAL TESTS


DATE DEC. 1980




SKETCHES
AT
FAILURE




TEST NO. T543.1



TEST NO. T543.2



TEST NO. T543.3



TEST NO. T543.4

TEST NO. / SYMBOL	INITIAL CONDITIONS			CONDITIONS BEFORE SHEAR				FINAL CONDITIONS		RATE OF STRAIN, PERCENT PER MINUTE
	INITIAL WATER CONTENT, %	INITIAL DRY UNIT WEIGHT, pcf	SAMPLE HEIGHT & DIAMETER, in.	INITIAL STRESSES $\sigma_1 = \sigma_3$, psf	FINAL BACK PRESSURE, psf	VOLUMETRIC STRAIN, %	PORE PRESSURE RESPONSE, %	FINAL WATER CONTENT, %	FINAL DRY UNIT WEIGHT, pcf	
T543.1	22.2	101.7	2.87	4320	10080	1.07	95	23.4	102.8	-
T543.2	24.5	97.8	2.87	440	7200	0.73	97	24.5	98.5	-
T543.3										
T543.4										

SOIL DESCRIPTION: GREY FINE SAND, SOME SILT


LIQUID LIMIT _____ PLASTIC LIMIT _____ SPECIFIC GRAVITY (SM) _____

SURRY MOUNTAIN DAM
SURRY, N.H.


TRIAXIAL COMPRESSION TESTS (MONOTONIC)

BORING NO. SMI TEST SERIES
SAMPLE T2 NO. 54
DEPTH 35.4' - 36.4' DATE DEC. 1980

SHEAR STRESS,



TOTAL NORMAL STRESS,



SOIL DESCRIPTION: GREY FINE SAND, SOME SILT
 LIQUID LIMIT _____ PLASTIC LIMIT _____ SPECIFIC GRAVITY _____


FAILURE CRITERIA _____

REMARKS _____

SURRY MOUNTAIN DAM
 SURRY, N.H.

MOHR STRENGTH ENVELOPE
 TRIAXIAL COMPRESSION
 TESTS (MONOTONIC)

BORING NO. SMI TEST SERIES
 SAMPLE T2 NO. 54
 DEPTH 35.4'-36.4' DATE DEC. 1980




TEST No.	SYM.	BORING No.	DEPTH (ft.)	INITIAL CONDITIONS			CONDITIONS BEFORE LOADING					FINAL CONDITIONS	
				w_n (%)	γ_d pcf	HT. DIA.	$\sigma_1 = \sigma_3$ psf	u_b psf	e_v (%)	β (%)	e_c	w_n (%)	γ_d pcf
T53.3.2	●	SMI	26.3-27.7	6.7	92.2	6000/2.900	4320	8640	1.51	95	0.81	31.5	93.6

SURRY MOUNTAIN DAM
SURRY, N.H.


SUMMARY PLOT
MONOTONIC TRIAXIAL TESTS

DATE DEC. 1980

SHEAR STRESS,



TOTAL NORMAL STRESS,




SOIL DESCRIPTION: GREY SILT AND FINE SAND (ML)
 LIQUID LIMIT _____ PLASTIC LIMIT _____ SPECIFIC GRAVITY _____

FAILURE CRITERIA _____

REMARKS _____

SURRY MOUNTAIN DAM
MOHR STRENGTH ENVELOPE
TRIAxIAL COMPRESSION
TESTS

BORING NO. SM1 TEST SERIES
 SAMPLE T1 NO. 53
 DEPTH 26.3'-27.7' DATE DEC. 1980



SKETCHES
AT
FAILURE




TEST NO. T533.2



TEST NO. _____



TEST NO. _____



TEST NO. _____


TEST NO./SYMBOL	INITIAL CONDITIONS			CONDITIONS BEFORE SHEAR				FINAL CONDITIONS		RATE OF STRAIN, PERCENT PER MINUTE
	INITIAL WATER CONTENT, %	INITIAL DRY UNIT WEIGHT, pcf	SAMPLE HEIGHT & DIAMETER, in.	INITIAL STRESSES $\sigma_1 = \sigma_3$, psf	FINAL BACK PRESSURE, psf	VOLUMETRIC STRAIN, %	PORE PRESSURE RESPONSE, %	FINAL WATER CONTENT, %	FINAL DRY UNIT WEIGHT, pcf	
T533.2	6.7	92.2	6.000	4320	8640	1.51	95	31.5	936	1

SOIL DESCRIPTION: GREYSILT AND FINE SAND (ML)

LIQUID LIMIT _____ PLASTIC LIMIT _____ SPECIFIC GRAVITY _____

SURRY, MOUNTAIN DAM SURRY, N.H. TRIAxIAL COMPRESSION TESTS

BORING NO. SMI _____ TEST SERIES
SAMPLE T1 _____ NO. 53
DEPTH 26.3-27.7' DATE DEC.1980



ϵ_{pp} = DOUBLE AMPLITUDE STRAIN

σ_{ee} = CYCLIC DEVIATOR STRESS ($\sigma_1 - \sigma_3$)

○, △ = NUMBER OF CYCLES TO $\epsilon_{pp} = 5\%$

●, ▲ = NUMBER OF CYCLES TO $\epsilon_{pp} = 10\%$

TEST NO. / SYMBOL 531 532

INITIAL CONDITIONS	WATER CONTENT	27.9%	29.3%	%	%	%
	DRY DENSITY pcf	93.6	91.2			
	RELATIVE DENSITY %	-	-			
	SAMPLE DIAMETER in.	2.830	2.830			
	SAMPLE WEIGHT lb.	5.720	5.640			
CONDITIONS BEFORE LOAD APPLICATION	FINAL BACK PRESSURE psf	7200	7200			
	INITIAL EFFECTIVE STRESS psf	5760	5760			
	VOLUMETRIC STRAIN	2.4%	2.7%	%	%	%
	PORE PRESSURE RESPONSE	97	96			
FINAL CONDITIONS	WATER CONTENT	26.5%	28.5%	%	%	%
	SKETCH OF SAMPLE AT END OF TEST					

LOAD APPLICATION
RATE 1 1

BORING No. SM1 SAMPLE No. T1

DEPTH 26.3' - 27.7'


SOIL DESCRIPTION GREY SILT AND
FINE SAND (ML)

ATTERBERG LIMITS

LIQUID LIMIT _____% , PLASTIC LIMIT _____%

SURRY MOUNTAIN DAM
SURRY, N.H.

SUMMARY PLOT
SHEAR STRESS RATIO vs CYCLES
DATE DEC. 1980




SURREY MOUNTAIN DAM
SURREY, N.H.

GRADATION TESTS

BORING NO. SM1 TEST SERIES
 SAMPLE NO. TI
 DEPTH 27.0'-27.2' DATE DEC. 1980

TEST NO.	SYM.	MATERIAL SOURCE	REMARKS
S/H 53.1		BORING SM1 SAMPLE TI DEPTH 27.0' - 27.2'	GREY SILT AND FINE SAND (ML)



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	


UNIFIED SOIL CLASSIFICATION SYSTEM

TEST NO.	SYM.	MATERIAL SOURCE	REMARKS
S/H 54.1		BORING SM1 SAMPLE T2 DEPTH 35.9'-36.4'	GREY UNIFORM FINE SAND, SOME SILT (SM)

GRADATION TESTS

SURREY MOUNTAIN DAM
SURREY, N.H.

BORING NO. SM1 TEST SERIES
 SAMPLE T2 NO. 54
 DEPTH 35.9'-36.4' DATE DEC. 1980



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	


UNIFIED SOIL CLASSIFICATION SYSTEM

TEST NO.	SYM.	MATERIAL SOURCE	REMARKS
S/H 36.1		BORING SMI SAMPLE S4 DEPTH 18.5' - 20.0'	GREY SILT & CLAY OF LOW TO MEDIUM PLASTICITY, TRACE FINE SAND (CL)

SURREY MOUNTAIN DAM
SURREY, N.H.

GRADATION TESTS

BORING NO. SM1 TEST SERIES
 SAMPLE NO. S4 NO. 36
 DEPTH 18.5'-20.0' DATE NOV. 1980





GRADATION TESTS

SURREY MOUNTAIN DAM
SURREY, N.H.

BORING NO. SM1 TEST SERIES
 SAMPLE NO. S7
 DEPTH 48.0'-49.5' DATE NOV 1980

TEST NO.	SYM.	MATERIAL SOURCE	REMARKS
S38.1		BORING SM1 SAMPLE S7 DEPTH 48.0'-49.5'	GREY SILT, AND FINE SAND (ML)






SURREY MOUNTAIN DAM
SURREY, N.H.

GRADATION TESTS

BORING NO. SM2 TEST SERIES
 SAMPLE NO. S7 NO. 43
 DEPTH 34.5'-36.0' DATE NOV. 1980

TEST NO.	SYM.	MATERIAL SOURCE	REMARKS
H43.1		BORING SM2 SAMPLE S7 DEPTH 34.5'-36.0'	GREY CLAYEY SILT OF SLIGHT PLASTICITY (ML)



COBBLES	GRAVEL		SAND			SILT OR CLAY
	COARSE	FINE	COARSE	MEDIUM	FINE	

UNIFIED SOIL CLASSIFICATION SYSTEM

TEST NO.	SYM.	MATERIAL SOURCE	REMARKS
S44.1		BORING SM2 SAMPLE S9 DEPTH 44.5'-46.0'	GREY SILT, LITTLE FINE SAND (ML)

GRADATION TESTS

SURREY MOUNTAIN DAM
SURREY, N.H.

BORING NO. SM2 TEST SERIES
 SAMPLE NO. S9
 DEPTH 44.5'-46.0' DATE NOV. 1980

EXHIBIT D

PSEUDO-STATIC EARTHQUAKE STABILITY ANALYSES*

<u>SUBJECT</u>	<u>PAGE</u>
Summary of Analyses	D-1
Pseudo-static Analyses of Upstream Slope	D-3
Pseudo-static Analyses of Downstream Slope	D-7

*The material in this exhibit was obtained from report entitled "Earthquake Design and Analyses for Corps of Engineers Dams, Stability Analyses by the Coefficient Method, Completed New England Division Dams", August 1980.

SURREY MOUNTAIN DAM

The pseudo-static analysis of Surrey Mountain Dam is based on the information contained in the following documents:

Surry Mountain Dam - Analysis of Design, Corps of Engineers, U. S. Army, U. S. Engineer Office, Providence, Rhode Island, Revised July 1939.

Cross Section Analyzed

The cross section at Sta 11+00 (Plate 42 in the Design Memorandum) was analyzed for stability of the upstream and downstream slopes. This is the maximum height section of the dam.

Embankment and Foundation Materials

The shear strengths and unit weights adopted for the pseudo-static analyses were based on the data presented in the Design Report. The shear strength data in the Design Report is discussed below for each material, numbered in accordance with the material numbers presented in Figs. A227 to A234. Comments are made when the shear strength adopted for the pseudo-static analysis was not based on data given in the Design Report.

1. Dumped Rock. No strength for the dumped rock was given in the Design Report. The strength used for the pseudo-static analysis was selected on the basis of experience with similar materials.
2. Pervious Fill. The drained shear strength data in the Design Report are based on the results of direct shear tests.
3. Random Impervious. The shear strength parameters presented in the Design Report were based on the results of direct shear tests.
4. Select Impervious. The shear strength data presented in the Design Report were based on the results of direct shear tests.

5. Foundation Sand. The shear strength data presented in the Design Report correspond to direct shear tests.
6. Foundation Silt. Shear strength tests on the silt presented in the Design Report incorporated varying rates of shear but they were probably all drained tests. The shear strength value selected in the Design Report corresponded to the lowest range of values measured.

Selection of Phreatic Surface



Approximate phreatic surfaces for various pool elevations were constructed using the analytical solutions for location of the seepage exit point presented by R. Lo (1969). The horizontal permeability of the impervious zone was assumed to be nine times the vertical permeability. Based on the permeability values presented on p. 39 of the Design Memorandum, the permeability of the Random Impervious material was taken to be 100 times that of the Select Impervious material and, therefore, the Random Material downstream of the Select Impervious core was assumed to be completely drained. The phreatic surfaces used for the pseudo-static analysis are somewhat different than the phreatic surface shown on Plate 46 in the Design Memorandum.

Potential Failure Surfaces Analyzed

Potential failure surfaces analyzed for the upstream and downstream slopes were circular surfaces extending from the crest and upper portion of the slope behind the crest to the break in slope at El 520, the lower portion of the slope in the vicinity of the toe, and the ground surface beyond the toe.

Comments on Results

The stability analyses presented in the Design Memorandum consist of rapid drawdown and "complete capillary saturation" analyses using stability charts based on the Friction-Circle Method and a sliding-wedge analysis for a deep failure through the foundation silt (Material No. 6 in Figs. A227 to A234) which is apparently an analysis for the condition at the end of construction. A meaningful comparison cannot be made between the analyses presented in the Design Memorandum and the static analyses performed for the present investigation.



Material	Unit Weights		Shear Strength					
	γ_m pcf	γ_{sat} pcf	S		R		Adopted	
			c ksf	ϕ deg	c ksf	ϕ deg	c ksf	ϕ deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0
 Minimum Computed Factor of Safety: 2.03
 Critical Pool Elevation: 500

U.S. Corps of Engineers
 Waltham, Massachusetts

Pseudo-Static Analysis
 New England Dams



SURREY MOUNTAIN DAM
 Upstream Slope
 Sta 11+00



GEOTECHNICAL ENGINEERS INC.
 WINCHESTER • MASSACHUSETTS

Project 80678

July 23, 1980 Fig. A227



Material	Unit Weights		Shear Strength					
	γ_m pcf	γ_{sat} pcf	S		R		Adopted	
			c ksf	ϕ deg	c ksf	ϕ deg	c ksf	ϕ deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0.05g
 Minimum Computed Factor of Safety: 1.61
 Critical Pool Elevation: 510

U.S. Corps of Engineers
 Waltham, Massachusetts



GEOTECHNICAL ENGINEERS INC.
 WINCHESTER, MASSACHUSETTS

Pseudo-Static Analysis
 New England Dams

Project 80678

SURREY MOUNTAIN DAM
 Upstream Slope
 Sta 11+00

July 23, 1980 Fig. A22B



Material	Unit Weights		Shear Strength					
	γ_m pcf	γ_{sat} pcf	S		R		Adopted	
			c ksf	ϕ deg	c ksf	ϕ deg	c ksf	ϕ deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0.10g

Minimum Computed Factor of Safety: 1.32

Critical Pool Elevation: 510

U.S. Corps of Engineers
Waltham, Massachusetts



GEOTECHNICAL ENGINEERS INC.
WINCHESTER • MASSACHUSETTS

Pseudo-Static Analysis
New England Dams

Project 80678

SURREY MOUNTAIN DAM
Upstream Slope
Sta 11+00

July 23, 1980 Fig. A229



Earthquake Acceleration: 0.13g
 Minimum Computed Factor of Safety: 1.19
 Critical Pool Elevation: 510

Material	Unit Weights		Shear Strength					
	γ_m pcf	γ_{sat} pcf	S		R		Adopted	
			c ksf	ϕ deg	c ksf	ϕ deg	c ksf	ϕ deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

U.S. Corps of Engineers
 Waltham, Massachusetts




GEOTECHNICAL ENGINEERS INC.
 WINCHESTER • MASSACHUSETTS

Pseudo-Static Analysis
 New England Dams

SURREY MOUNTAIN DAM
 Upstream Slope
 Sta 11+00

Project 80678

July 23, 1980 Fig. A230



Material	Unit Weights		Shear Strength					
	γ_m	γ_{sat}	S		R		Adopted	
			c	ϕ	c	ϕ	c	ϕ
	pcf	pcf	ksf	deg	ksf	deg	ksf	deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0

Minimum Computed Factor of Safety: 1.86

Maximum Pool Elevation: 560

U.S. Corps of Engineers
Waltham, Massachusetts


GEOTECHNICAL ENGINEERS INC.
WINCHESTER • MASSACHUSETTS

Pseudo-Static Analysis
New England Dams

Project 80678

SURREY MOUNTAIN DAM
Downstream Slope
Sta 11+00

July 23, 1980 Fig. A231



Material	Unit Weights		Shear Strength					
	γ_d	γ_{sat}	S		R		Adopted	
	pcf	pcf	c ksf	ϕ deg	c ksf	ϕ deg	c ksf	ϕ deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	132	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0.05g

Minimum Computed Factor of Safety: 1.50

Maximum Pool Elevation: 560

U.S. Corps of Engineers
Waltham, Massachusetts




GEOTECHNICAL ENGINEERS INC.
WINCHESTER • MASSACHUSETTS

Pseudo-Static Analysis
New England Dams

SURREY MOUNTAIN DAM
Downstream Slope
Sta 11+00

Project 80678

July 23, 1980 Fig. A232



Material	Unit Weights		Shear Strength					
	γ_m	γ_{sat}	S		R		Adopted	
	pcf	pcf	c ksf	ϕ deg	c ksf	ϕ deg	c ksf	ϕ deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0.10g

Minimum Computed Factor of Safety: 1.26

Maximum Pool Elevation: 560

U.S. Corps of Engineers
Waltham, Massachusetts

Pseudo-Static Analysis
New England Dams


SURREY MOUNTAIN DAM
Downstream Slope
Sta 11+00



GEOTECHNICAL ENGINEERS INC.
WINCHESTER, MASSACHUSETTS

Project 80678

July 23, 1980 Fig. A233



Material	Unit Weights		Shear Strength					
	γ_m	γ_{sat}	S		R		Adopted	
			c	ϕ	c	ϕ	c	ϕ
	pcf	pcf	ksf	deg	ksf	deg	ksf	deg
1	110	132	0	40	-	-	0	40
2	130	136	0	40	-	-	0	40
3	135	139	0	37	-	-	0	37
4	140	142	0	34	-	-	0	34
5	132	132	0	37	-	-	0	37
6	125	125	0	25	-	-	0	25

Earthquake Acceleration: 0.13g

Minimum Computed Factor of Safety: 1.15

Maximum Pool Elevation: 560

U.S. Corps of Engineers
Waltham, Massachusetts



GEOTECHNICAL ENGINEERS INC.
WINCHESTER • MASSACHUSETTS

Pseudo-Static Analysis
New England Dams

Project 80678

SURREY MOUNTAIN DAM
Downstream Slope
Sta 11+00

July 23, 1980 Fig. A234